9. The tenderer must quote specific rates for all items both in words and figures.

10. The tenderer stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for Restoring Chickanter Tank Register No. 14e of Malur Taluk.

Items of work	Per	Rate	Quantity	Cost
		Rs. a. p		
Bund.				
Earthwork including watering and tamping and with lead and lift.	C.yds.		5,104	
Turfing to bund	S.yds.		4,088	
Removing and resetting old stone revetment	C.yds.		229	
New stone revetment	"		792	
Refixing grade stones after painting figuring, etc.	No.		17	
New grade stones	"		3	
Bench mark stones	"		2	
Index stones	"		14	
Register No. stone	"		1	
Gauge stones	"		4	
Cutting trenches and removing anthills and trees, etc	Grade		12	
Sluice.				
Examining and closing the leaks by the side of barrel and attending the sundry repairs.	Lump sum		...	
Waste weir at 50·00 Length of 130 feet.				
Clearing debries, etc.	Lump sum		...	
Removing the coping slabs of existing body wall	S.ft.		80	
Earthwork	C.yds.		360	
Surki concrete	C.ft.		407	
Burnt brick in surki mortar	"		916	
Burnt stone slabs new	S.ft.		331	
Refixing old slabs with mortar	"		166	
Plastering with surki mortar	Sqrs.		15·05	
Rough stone work new	C.yds.		21·5	
Resetting old stone revetment	"		11	
Jelly filling to scours including lead and lift ..	"		23	
Pin slabs	No.		11	
Toggles joints	"		26	
Grand total ..	..	...	...	
Contingency at 5 per cent ..	..	...	...	
Grand total ...	..	...	..	

Notice dated 12th February 1930.

Attention of the public is invited to the notification, published in the *Mysore* Part VI, page 208, dated 20th February 1930, calling for tenders for improving the Feeder Channel to Kangadhamana Tank, Chikkallapur Taluk.

Last date of tender is 2 P.M. on 10th March 1930.